

Installation Procedure for Sliding Door Units

Please take care to adhere to the installation procedure to ensure proper operation of your high quality Miglas door system. Failure to follow these steps will result in poor operation or malfunction and expensive service call costs to remedy poor installation by others.

- Take care in **sighting** and **packing** the sill for **straightness** – check with spirit level.
 - The jambs must be parallel, (check with straight edge and spirit level) and should be packed and fixed at approx 300 centres.
 - Check to confirm that frame is square by measuring diagonally corner to corner.
 - If the door is not absolutely parallel to the locking style, check and adjust door rollers to align the door with the closing style. If this is not carried out the lock will be hard to operate.
- * Please note that failure of the installer or end user to obey these instructions will free Miglas of any and all product liability.**